

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-093-21,379,0000

LEASE NAME Williams "K"

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1-8

4290 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 8 TWP. 21S RGE. 35 (E) or (W)

COUNTY Kearny

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 3017 N. Cypress, Wichita, KS 67226-4003

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 8-12-94

Plugging Commenced 8-11-94

Plugging Completed 8-12-94

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To   | Size   | Put in | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
|           |         | 0    | 383' | 8-5/8" | 383'   | None       |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Plug and abandon using Halliburton with 315 sacks of 60/40 Pozmix, 6% gel, 1/4# floccle. Plugged with 100 sacks at 3200', 50 sacks at 2050', 80 sacks at 1150', 50 sacks at 425'. 15 sacks in rathole. 10 sacks in mousehole. Complete 1:00 p.m. 8-12-94.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sweetman Drilling, Inc. License No. 5003

Address 3017 N. Cypress, Wichita, KS 67226-4003

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3017 N. Cypress, Wichita, KS 67226-4003

RECEIVED BY COMMISSION  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS 67226-4003

SUBSCRIBED AND SWORN TO before me this 16th day of August, 1994

DEBORAH ANN PAULUS  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 12-31-96

Deborah Ann Paulus  
NOTARY PUBLIC  
WICHITA, KANSAS  
AUG 22 1994