


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800-Bitting Building
Wichita, Kansas

Hodgeman County. Sec. 6 Twp. 21 Rge. 25W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Bennett & Roberts Drilling Co.
Lease Name McVickers Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/15 19 54
Application for plugging filed 9/15 verbally 19 54
Application for plugging approved 9/15 verbally 19 54
Plugging commenced 9/15 19 54
Plugging completed 9/15 19 54
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 491.3 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	233'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set at 230' w/ 1/4 sack hulls and 20 sacks cement through drill pipe.
Top plug set at 35' and 1/4 sack hulls and 10 sacks cement.

9-20-1954
STATE OF KANSAS
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BENNETT & ROBERTS DRILLING CO.

(Signature) Harold Wurst
Russell, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 54

My commission expires 6/17/58 Clara Hummel Notary Public.

24-7388-5 3-53,20M
PLUGGING
FILE SEC 6 T 21 R 25W
BOOK PAGE 64 LINE 30

Bennett & Roberts Drilling Co.
McVickers #1

SW SW. NW Sec. 6-21-25
Hodgeman County, Kansas

Comm: 8/2/54
Comp: 9/15/54

Tops:	Cim. Anhyd.	980
	Heebner Shale	3730
	Toronto Lime	3752
	Brown Lime	3787
	Lansing K.C.	3808
	Basal K.C.	4098
	Marmaton	4118
	Cherokee	4349
	Conglomerate	4389
	Mississip. Dolo.	4413
	Misner Sand	4702
	Viola	4711
	Simpson Shale	4898

Set 8 5/8" Casing @ 233'

R.T.D. 4913

Elev. 2401RB

<u>Formation:</u>	<u>Depth:</u>
Surface Clay & Sand	70'
Sand	100
Blue & Gray Shale	180
Sand & Shale	2009
Blue Shale	260
Shale	680
Shale & Shell	780
Red Bed	980
Anhydrite	1010
Red Bed & Shale	1035
Red Bed	1285
Red Bed, Shale & Shells	1690
Shale & Shells	2275
Shale & Lime	2340
Lime	2415
Lime & Shale	3260
Shale	3385
Lime & Shale	3603
Lime	4311
Sandy Shale & Lime	4360
Lime	4399
Lime & Chert	4403
Chert	4407
Conglomerate	4415
Lime	4541
Lime & Chert	4619
Chert	4636
Lime & Chert	4654
Lime	4677
Lime & Chert	4682
Lime	4700
Lime & Chert	4757
Lime	4775
Lime & Chert	4898
Shale	4913

STATE OF KANSAS)
RUSSELL COUNTY)

RECEIVED
STATE CORPORATION COMMISSION
CONSOLIDATED DIVISION
Topeka, Kansas

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By Harold W. Wurst

Subscribed and sworn to before me this 17th day of September, 1954.

Clara Hummel
Notary Public

My Commission Expires 6/17/58

PLUGGING
WELL SEC 6-21-25W
BOOK PAGE 14 LINE 30