


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County, Sec. 35 Twp. 21 Rge. 24 E/W
Location as "NE/CNW¹/₄SW¹/₄" or footage from lines
C NE SW
Lease Owner Donald C. Slawson
Lease Name Goebel 'D' Well No. 2
Office Address 408 One Twenty Bldg., Wichita 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Date Well completed 19
Application for plugging filed 4/14/76 19
Application for plugging approved 4/15/76 19
Plugging commenced 4/27/76 19
Plugging completed 4/27/76 19
Reason for abandonment of well or producing formation
no longer needed as SWDW. Producer previously plugged
If a producing well is abandoned, date of last production
Not applicable 19
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas Jr.
Producing formation Cedar Hills Depth to top 1095 Bottom 1700 Total Depth of Well 4296
Disposal Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	FEET IN	PULLED OUT
Cedar Hills	Salt Water	1095'	1700'	8-5/8	606'	none
				4-1/2"	1095'	none
				2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 1700' feet to 0 feet for each plug set.

Tubing packer unseated @ 947'. Cement pumped down 2" tubing until circulated out casing - tubing annulus. Shut in casing head valve and displaced remainder of cement through tubing. Total cement pumped 100 sax. Shut in tubing head valve.

MAY 20 1976
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services.

STATE OF Kansas COUNTY OF Sedgwick SE


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Kemsberg
James C. Kemsberg
408 One Twenty Building, Wichita 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May 1976

My commission expires January 17, 1977

Mary Lou Taylor
Mary Lou Taylor Notary Public



WELL LOG

LEASE OWNER: Donald C. Slawson
 408 One Twenty Building
 Wichita, Kansas 67202

LEASE: Goebel 'D' #2
 C NE SW Sec. 35-21-24W
 Hodgeman County, Kansas

COMMENCED: April 3, 1974

COMPLETED: April 12, 1974

TOTAL DEPTH: 4296 feet

CASING: Set 8 5/8" @ 606 feet w/400 sx

CONTRACTOR: Slawson Drilling Company, Inc.

0-80	Sand
80-175	Shale & Shells
175-620	Surface Hole
620-1167	Shale & SHELLS
1167-1380	Sand
1380-1703	Shale & Sand
1703-1745	Anhydrite
1745-2448	Shale & Shells
2448-4165	Lime & Shale
4165-4296	Lime
RTD 4296	

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

RECEIVED
 STATE CONSERVATION COMMISSION
 APR 15 1976
 CONSERVATION DIVISION
 Wichita, Kansas

I, JAMES C. REMSBERG, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the Goebel 'D' #2.

James C. Remsberg
 JAMES C. REMSBERG

Subscribed and sworn to before me this 29th day of April, 1974.

Dolores B. Coady
 DOLORES B. COADY, Notary Public

My Commission Expires:

DOLORES B. COADY
 STATE NOTARY PUBLIC
 SEDGWICK COUNTY, KANSAS
 Comm. Expires Mar. 7, 1976