


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Hodgeman County. Sec. 10 Twp. 21 Rge. 25 (SE) (W)  
Location as "NE/CNW/SW" or footage from lines SWSW SE  
Lease Owner Hilton Drilling Company, Inc.  
Lease Name Ploger Well No. 1  
Office Address 925 Patton Road, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 17, 19 57  
Application for plugging filed April 20, 19 57  
Application for plugging approved April 22, 19 57  
Plugging commenced April 27, 19 57  
Plugging completed May 2, 19 57  
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4480 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280'	none
				5-1/2"	4478'	3739'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 4424' to 4320' and dumped 5 sacks cement; pulled casing to 850', mixed and pumped 25 sacks Davis-gel, pulled casing to 550', mixed and pumped 75 sacks cement. Pulled remainder of casing, checked cement fillup to 240' mudded to 35' set 10' rock bridge, mixed and poured 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company  
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Henry Peacock, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock  
Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of May 19 57

Mildred Hobbie  
Notary Public.

My commission expires \_\_\_\_\_

24-7968-5 3-53-20M STAT. CORPORATION COMMISSION

MILDRED HOBBIIE  
MY COMMISSION EXPIRES MARCH 6, 1958

MAY 10 1957  
PLUGGING  
CONSERVATION DIVISION  
FILE SEC 10 T 21 R 25 W SE  
Wichita, Kansas  
BOOK PAGE 1 LINE 37

## DRILLER'S LOG

COMPANY: Hilton Drilling Company, Inc.

LOCATION: SW SW SE

Sec. 10-21S-25W

CONTRACTOR: Hilton Drilling Company, Inc.

Hodgeman County, Kansas

FARM NAME: Ploger No. 1

ELEVATION: 2312 D.F.

COMMENCED: January 29, 1957

Casing Used: 8-5/8" set @ 281' w/225 sxs.  
5-1/2" set @ 4478' w/150 sxs.


COMPLETED: February 17, 1957

Clay	15
Sand	30
Post Rod & Shale	40
Shale and Sand	155
Shale	281
Shale and Shells	640
Red Bed, Shale & Shells	864
Red Bed and Shale	925
Gypsum	965
Shale and Shells	1030
Sand and Shale	1190
Shale and Shells	1562
Anhydrite	1600
Shale and Shells	1795
Shale, Lime and Shells	1980
Shale and Lime	2355
Lime	2425
Shale and Lime	2540
Lime	3085
Shale and Lime	3490
Lime	4232
Lime and Chert	4480
Total Depth	4480

STATE OF KANSAS     )  
                                  ) SS.  
COUNTY OF BARTON )

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above-described.

HILTON DRILLING COMPANY, INC.



Subscribed and sworn to before me this 19th day of February, 1957

  
 Notary Public

 MILDRED HOBBI  
 MY COMMISSION EXPIRES MARCH 6, 1958

 RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 22 1957  
 CONSERVATION DIVISION  
 Wichita, Kansas

 PLUGGING  
 FILE SEC. 10 T. 21 R. 25W  
 BOOK PAGE 7 LINE 37