


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

McPherson County, Sec. 23 Twp. 21 Rge. 2W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SE SW NE
Lease Owner A. Scott Ritchie
Lease Name Unruh #2 Well No. _____
Office Address Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/30/77 _____ 19____
Plugging completed 10/18/77 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3355
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	163	none
				4 1/2"	3027'	2013'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug at 2750', shot pipe at 2648', 2567', 2530', 2444', 2207', 2010', pulled pipe.
Bailed hole 185 to 175' and set rock bridge, ran 30 sacks cement. Mudded to 40, set rock bridge to 30' and ran 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

OCT 28 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASTING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of October, 19 77



Margaret Melcher
Notary Public.

My commission expires _____

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

A. SCOTT RICHIE - OPERATOR

UNRUH # 2
SE-SW-NE 23-21-2
McPHERSON COUNTY, KANSAS

T. D. 3355
ELEV. 1491 KB

COMMENCED: 2-16-77
COMPLETED: 2-23-77

CASING:

8 5/8 set at 163'
4 1/2 set at 3027'

CEMENT:

130 sx cement
75 sx cement

FORMATION

DEPTH

Clay, shale & sand streak
Shale & Lime
Lime & Shale
Chert, lime & shale
Sand
Shale

0 - 163
163 - 590
590 - 2953
2953 - 3335
3335 - 3340
3340 - 3355

RECEIVED
STATE COMMISSION
JUL 15 1977
CONSERVATION DIVISION
Wichita, Kansas

TOPS

Lansing
Miss.
Kinderhook
Misener sand
Maquoketa

2309
2953
3261
3335
3340

AFFIDAVIT

STATE OF KANSAS, COUNTY OF BARTON


I, Wayne Dobbs, of the L.D. Drilling Company

being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Wayne Dobbs
Wayne Dobbs

Subscribed and sworn to before me on this 25th day of Feb. 1977

My commission Expires: 12-11-79



Elsie J. Learned
Notary Public Elsie J. Learned