


STATE OF KANSAS  
STATE CORPORATION COMMISSION

## WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plot

McPherson County. Sec. 23 Twp. 21 Rge. 2W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SE NE SW

Lease Owner Homer G. Krehbiel  
Lease Name Unruh Well No. 1  
Office Address 1343 N. Maple, McPherson, Kansas 67460  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole

Date Well completed January 20, 1979  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 19  
Plugging completed January 20, 1979  
Reason for abandonment of well or producing formation  
Dry Hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation                      Depth to top                      Bottom                      Total Depth of Well                       
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		0	133'	8 5/8"	133'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from                      feet to                      feet for each plug set.

Set first plug at 125' with 20 sacks of cement. Filled with mud  
to 40' and set plug with 10 sacks of cement, 2 sacks in rathole.  
Plugging completed at 7:30 A. M., January 20, 1979 by State Plugger  
Gilbert Toman, Holyrood, Kansas.

1-30-1979  
RECEIVED  
STATE CORPORATION COMMISSION

JAN 30 1979

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Blackstone Drilling, Inc., Box 1184, McPherson, Kansas 67460

STATE OF Kansas COUNTY OF McPherson, ss.  
Homer G. Krehbiel (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Homer G. Krehbiel  
1343 N. Maple, McPherson, Kansas 67460  
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of January, 1979

Marie E. Krehbiel  
Notary Public.

My commission expires March 6, 1981

MARIE E. KREHBIEL  
STATE NOTARY PUBLIC  
McPHERSON COUNTY, KANS.  
MY APPT. EXP. MAR. 6, 1981



# Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

January 22, 1978

COMPANY: HOMER G. KREHBIEL  
 CONTRACTOR: BLACKSTONE DRILLING, INC.  
 FARM: UNRUH #1  
 LOCATION: SE NE SW Section 23-21-2W,  
 McPherson County, Kansas  
 COMMENCED: January 11, 1979  
 COMPLETED: January 20, 1979  
 ELEVATION:

0	to	475
475	to	1109
1109	to	1300
1300	to	1770
1770	to	1935
1935	to	2240
2240	to	2470
2470	to	2670
2670	to	2959
2959	to	3252
3252	to	3335
3335	to	3358
		3358

Shale  
 Shale & Lime  
 Shale  
 Lime & Shale  
 Shale & Lime  
 Lime & Shale  
 Shale & Lime  
 Lime & Shale  
 Shale & Lime  
 Mississippi  
 Kinderhook  
 Hunton  
 T. D.

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 30 1979

CONSERVATION DIVISION  
 Wichita, Kansas

Cut 12½" hole to 131' and run 133' of 8 5/8" surface pipe, cemented with 100 sacks of cement at 131'. Plug down at 3:00 P. M., January 11, 1979. Cut 7 7/8" hole to 3358'. Hole dry and abandoned. Set bottom plug at 125' with 20 sacks of cement. Filled with mud to 40' and set plug with 10 sacks, 2 sacks in rathole. Plugging completed by State Plugger, Gilbert Toman, Holyrood, Kansas at 7:30 A. M., January 20, 1979.

TOPS: MISSISSIPPI - 2959' KINDERHOOK - 3252' HUNTON - 3335'


Measurements taken from K. B.

## CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Unruh #1, located on the SE NE SW, Section 23-21-2W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

  
 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 22nd day of January, 1979.

  
 Johnnie L. Schmidt - Notary Public

