


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

McPherson County, Sec. 23 Twp. 21 Rge. 2W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW SE SW

Lease Owner John J. Darrah & Royce J. Graber
Lease Name Stucky #1 Well No. 1
Office Address 1010 Century Plaza Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry
Date Well completed September 1, 1979
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 19
Plugging completed September 1, 1979
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay & Sand		0	60'	8 5/8"	60'	None
Shale		60'	130'	8 5/8"	70'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug with 20 sacks of cement. Filled with mud to 40' and set plug with 10 sacks, 2 sacks in rathole. Plugging completed at 11:30 A. M., Sept. 1, 1979 by Gilbert Toman, State Plugger, Holyrood, Kansas.

RECEIVED 9-13-1979
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc., Box 1184, McPherson, Ks. 67460

STATE OF Kansas COUNTY OF Sedgwick
John J. Darrah & Royce J. Graber (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


JOHN J. DARRAH & ROYCE J. GRABER

(Signature) BY: Royce J. Graber
@ 1 Box 184 McPherson
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of September, 19

Jeanne C. Kepner
Jeanne C. Kepner Notary Public.

My commission expires





Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

SEPTEMBER 4, 1979

COMPANY: JOHN W. DARRAH & ROYCE J. GRABER
CONTRACTOR: BLACKSTONE DRILLING, INC.
FARM: STUCKY #1
LOCATION: NW SE SW Section 23-21-2W,
McPherson County, Kansas
COMMENCED: August 25, 1979
COMPLETED: September 1, 1979
ELEVATION:

0	to	60	Clay & Sand
60	to	620	Shale
620	to	950	Shale & Lime
950	to	1260	Lime & Shale
1260	to	1790	Shale
1790	to	2550	Shale & Lime
2550	to	2890	Lime & Shale
2890	to	2990	Shale & Lime
2990	to	3264	Mississippi
3264	to	3330	Shale
3330	to	3358	Hutton
		3358	T. D.

Cut 12 1/2" hole to 126' and run 128' of 6 5/8" surface casing, cemented with 100 sacks of cement at 126'. Plug down at 11:30 A. M., August 25, 1979. Hole dry and abandoned. Set bottom plug at 120' with 20 sacks of cement. Filled with mud to 40' and set plug with 10 sacks, 2 sacks in rathole. Plugging completed at 11:30 A. M., September 1, 1979. Gilbert Toman, State Plugger, Holyrood, Kansas.

TOPS: MISSISSIPPI - 2990' HUTTON - 3330'

Measurements taken from K. B.


CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Stucky #1, located on the NW SE SW Section 23-21-2W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 4th day of September, 1979.


Johnnie L. Schmidt - Notary Public



RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1979

STATE CORPORATION DIVISION
Wichita, Kansas