

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Hodgeman County, Sec. 34 Twp. 21S Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines app. C SE NW

Lease Owner Oasis Petroleum, Inc.

Lease Name Smith Well No. 2

Office Address 800 Sutton Place, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed July 24 19 72

Application for plugging filed July 24 19 72

Application for plugging approved July 24 19 72


Plugging commenced July 24 19 72

Plugging completed July 24 19 72

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Edger Eves

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4752 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	565'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 560' with 35 sacks cement. 2nd plug & bridge to hold Kelly @ 45' with 15 sacks cement. 2 sacks in rat hole. Job by Howco. Job complete at 4:30 p.m. 7-24-72.

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1972
CONSERVATION DIVISION
Wichita, Kansas
8-23-1972

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

Address 800 Sutton Place, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jack G. Paulsen (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen
800 Sutton Place, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 1972.

My commission expires June 28, 1974. Jean S. Taylor Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

7/23 1972

CONSERVATION DIVISION
Wichita, Kansas

SMITH #2
C SE NW
Section 34-21S-24W
Hodgeman County, Kansas

Commenced: July 13, 1972
Completed: July 24, 1972

OPERATOR: OASIS PETROLEUM, INC.

From	Depth To	Formation	Remarks
0	570	Surface	Ran 13 joints of used 28# 8 5/8" csg. set @ 565' cemented w/300 sks common, 3% CC, 2% Gel P.D. @ 10:30 PM 7/23/72 Cement Circ.
570	600	Shale	
600	1180	Shale-Shells	
1180	1732	Sand-Shale	
1732	1771	Anhydrite	
1771	1808	Shale	
1808	2175	Shale-Shells	
2175	2468	Shale-Lime	
2468	2587	Lime-Shale	
2587	2800	Lime	
2800	3345	Shale-Lime	
3345	3905	Lime-Shale	
3905	3955	Shale-Lime	
3955	4692	Lime	
4692	4712	Coring	
4712	4752	Lime (Miss)	
4752	TD		DRY AND ABANDONED

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE NW, Section 34-21S-24W, Hodgeman County, Kansas to the best of my knowledge and belief.


James S. Sutton II
James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 26th day of July, 1972, personally appeared James S. Sutton, II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
Marjorie Hall, Notary Public



My commission expires Nov. 29, 1975.