


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Hodgeman County, Sec 34 Twp 21S Rge. (E) 24 (W)  
Location as "NE/CNWSW" or footage from lines 660' FNL & 660' FEL (NE NE)  
Lease Owner Oasis Petroleum, Inc.  
Lease Name Everton Well No. 5  
Office Address 3535 NW 58th Street, Oklahoma City, Okla. 73112  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-12 19 74  
Application for plugging filed 6-13 19 74  
Application for plugging approved 6-12 19 74  
Plugging commenced 6-12 19 74  
Plugging completed 6-12 19 74  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Edgar J. Eves  
Producing formation None Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				8 5/8"	687'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Conditioned hole with heavy mud. Spotted 80 sx cement plug from 600 to 700'. Set 15 sx cement plug from 45' to surface. Cut off surface pipe 3' below G.L. and welded on identifying steel cap.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 17 1974  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Continental Oil Company  
Address

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
L. W. Shirkey (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Shirkey Administrative Supervisor  
(Address)

Subscribed and sworn to before me this 13th day of June, 1974  
My commission expires 1-3-77



Frank S. Carr Notary Public.

DRILLERS LOG

*Dup*

RECEIVED  
STATE CORPORATION COMMISSION

JUL 10 1974

CONSERVATION DIVISION  
Wichita, Kansas

COMPANY: Continental Oil Co.  
3535 NW 58th Street  
Oklahoma City, Oklahoma

LEASE NAME: Everton #5  
660' FNL & 660' FEL  
Sec. 34-21-24W  
Hodgeman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
408 120 Building  
Wichita, Kansas 67202

TOTAL DEPTH: 4700 feet

COMMENCED: June 3, 1974

COMPLETED: June 12, 1974

CASING: Set 8 5/8" @ <sup>687'</sup>~~686'~~ w/375 sx

0-330	Shale
330-690	Shale & Shells
690-1105	Shale -Red Bed
1105-1390	Sand
1390-2196	Shale & Shells
2196-3980	Lime& Shale
3980-4700	Lime
RTD 4700	

STATE OF KANSAS )  
                                ) SS.  
COUNTY OF SEDGWICK )

I, James C. Remsberg, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log on the Everton #5 well.

*James C. Remsberg*  
JAMES C. REMSBERG

Subscribed and sworn to me on June 19, 1974.

*Dolores B. Coady*  
DOLORES B. COADY, NOTARY PUBLIC

MY COMMISSION EXPIRES:

