


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plot

McPherson County. Sec. 13 Twp. 21S Rge. 2W (~~EX~~) (W)
Location as "NE/CNW/SW" or footage from lines NW SW SE
Lease Owner Beacon Resources Corporation
Lease Name Dyck #3 Well No. _____
Office Address 312 Union Center Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 13, 19 69
Application for plugging filed January 13, 19 69
Application for plugging approved January 13, 19 69
Plugging commenced 5:00 PM, January 13, 19 69
Plugging completed 7:00 PM, January 13, 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3495' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8"	201.59'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 200'
25 sacks cement filled hole to 40'
Plugged with 10 sacks regular cement.
2 sacks regular cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF Kansas, COUNTY OF Rice, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 69.

Bernard Laudermilk
Bernard Laudermilk, Notary Public.

My commission expires _____

BERNARD LAUDERMILK, Notary Public
Commission Expires January 22, 1970

15.113.20061.0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- Dyck #3
Located: NW SW SE, Sec. 13-21S-2W, McPherson County, Kansas

OWNER: Beacon Resources Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 6, 1969
COMPLETED: January 13, 1969

TOTAL DEPTH: 3495'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 219 Surface Shale and Sand	Ran 5 joints Surface Casing 201.59'
219 - 480 Sand	Cemented 213 K.B. with 200 sacks Regular Cement with 3% cc, 2% gel.
480 - 875 Lime and Shale	Plug down 4:30 PM, 1-6-69
875 - 1194 Lime	
1194 - 2670 Lime and Shale	
2670 - 2818 Lime	
2818 - 3003 Lime and Shale	
3003 - 3175 Lime and Chert	
3175 - 3262 Lime	
3262 - 3330 Lime and Chert	
3330 - 3495 Lime	Plugged

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1969
CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- Dyck #3
Located: NW SW SE, Sec. 13-21S-2W, McPherson County, Kansas

OWNER: Beacon Resources Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 6, 1969
COMPLETED: January 13, 1969

TOTAL DEPTH: 3495'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 219	Surface Shale and Sand	Ran 5 joints Surface Casing 201.59'
219 - 480	Sand	Cemented 213 K.B. with 200 sacks Regular Cement with 3% cc, 2% gel. Plug down 4:30 PM, 1-6-69
480 - 875	Lime and Shale	
875 - 1194	Lime	
1194 - 2670	Lime and Shale	
2670 - 2818	Lime	
2818 - 3003	Lime and Shale	
3003 - 3175	Lime and Chert	
3175 - 3262	Lime	
3262 - 3330	Lime and Chert	
3330 - 3495	Lime	Plugged

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1969
CONSERVATION DIVISION
Wichita, Kansas