

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

T 21S NORTH R 16W

	11		
	*		

Locate well correctly on above Section Plat

Pawnee County, Sec. 11 Twp. 21S Rge. 16W (E) (W)
Location as "NE/CNWSW" or footage from lines CN/2 SE SW
Lease Owner: Carl Todd Drilling Company
Lease Name: Bowman Well No. 1
Office Address: 706-08 Union Center - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed: January 9 19 55
Application for plugging filed: August 16 19 56
Application for plugging approved: August 16 19 56
Plugging commenced: October 6 19 56
Plugging completed: October 9 19 56
Reason for abandonment of well or producing formation: Depleted

If a producing well is abandoned, date of last production: August 15 19 56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Brundege
Producing formation: _____ Depth to top: _____ Bottom: _____ Total Depth of Well: 3810 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	890'	None
				5-1/2"	3806'	3053'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3810' to 3790'
And ran 5 sacks of cement. Mudded the hole to 300', set a 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 35', set a rock bridge and ran 10 sacks of cement on top.
Plugging completed.

Name of Plugging Contractor: West Supply Co., Inc.
Address: Chase, Kansas
(If additional description is necessary, use BACK of this sheet)

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Carl Todd (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Todd
706 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 19 56

My commission expires December 14, 1957

Notary Public.

PLUGGING
FILE SEC. 11 T. 21 R. 16W
BOOK PAGE 90 LINE 39

OCT 16 1956
CONSERVATION DIVISION
Wichita, Kansas

THE CARL TODD DRILLING COMPANY
404 KFH Building
Wichita, Kansas

#1 Bowman
C N/2 SE SW Sec. 11-21-16W
Pawnee County, Kansas

COMMENCED: December 20, 1954
COMPLETED: January 4, 1955

ELEVATION: 1979 Kelly Bushing

CASING RECORD

0 - 20	Surface clay	3-5/8" casing set at 890' with	
20 - 60	Sand	225 sacks cement.	
60 - 285	Shale and sand		
285 - 405	Shale and Red Bed	5-1/2" OD 14. # J-55 casing set	
405 - 515	Sand	at 3806' with 125 sacks cement.	
515 - 575	Red Bed, shale and shells		
575 - 650	Shale, shells & sand streaks		
650 - 890	Shale and shells		
890 - 985	Shale and shells		
985 - 1015	Anhydrite		
1015 - 1140	Shale and sand	Topcka	3084
1140 - 1470	Shale and shells	Heebner	3349
1470 - 1545	Shale and salt	Toronto	3377
1545 - 1725	Shale and salt	Brown Lime	3442
1725 - 1990	Shale and shells	Penn. Congl.	3717
1990 - 2045	Sandy lime and shale	Viola	3737
2045 - 2125	Lime and shale	Simpson	3764
2125 - 2470	Shale and lime	Arbuckle	3806
2470 - 2600	Shale and lime	RTD	3810 1/2
2600 - 2715	Shale		
2715 - 3160	Shale and lime	DST 3802 - 10-1/2	
3160 - 3225	Lime and shale	Open 1 hour, recovered 960' gas,	
3225 - 3415	Lime	65' heavy oil cut mud, 60' free oil.	
3415 - 3445	Shale and lime	BHP 1120# 20".	
3445 - 3712	Lime		
3712 - 3760	Chert & shale		
3760 - 3797	Lime, chert and shale		
3797 - 3810-1/2	Shale and lime		
3810 - 1/2	Rotary Total Depth		

TOPS

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY

By: *Carl Todd*

RECEIVED
STATE COMMISSION
AUG 13 1955
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
COUNTY OF SEDGWICK

Subscribed and sworn to before me this 12th day of January, 1955.

D. D. [Signature]
Notary Public

My commission expires Dec. 14, 1957

PLUGGING
FILE SEC. 11 T. 21 R. 16W
BOOK PAGE 90 LINE 39