

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY PAWNEE SEC. 11 TWP. 21 RGE. 16 E/W  
Location as in quarters or footage from lines:  
330 ENL and 100 ENL S2 of SE4


Lease Owner HUPFER OIL & GAS  
Lease Name ROWMAN Well No. C-1  
Office Address 2309 Walnut Hays, Kansas 67601  
Character of Well Completed as Oil (Gas or Dry Hole):  
Date Well Completed June 18, 1982  
Application for plugging filed Verbal request  
Plugging commenced 4:30 P.M. Aug. 14, 1982  
Plugging completed 6:30 P.M. Aug. 14, 1982  
Reason for abandonment of well or producing formation  
Production non-commercial - water broke in.  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Locate Well  
correctly on above  
Section Platt.

Name of Conservation Agent who supervised plugging of this well Steve Durant  
Producing formation Arbuckle Depth to top 3818 bottom 3820 T.D. 3820  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	surface	0	970	8 5/8	970	none
	production	0	3818	5 1/2	3818	2209

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set Bridge Plug @ 3700. Plugged with pump truck as follows: 3 sx. gel, 70 sx cement, 10 sx. gel, 1 Hull and 80 sx. cement.

State plugger, Steve Durant witnessed plugging along with Dennis D. Hupfer.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing Box 169 Great Bend, Ks. 67530  
(See back side)

STATE OF Kansas COUNTY OF Ellis, ss.

Dennis D. Hupfer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Dennis D. Hupfer  
2309 Walnut Hays, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of September 19 82



Kristie A. Hutchinson  
STATE COMMISSIONER

My Commission expires: \_\_\_\_\_

SFP 0 8 1982

CONSERVATION DIVISION  
Wichita, Kansas

9-8-1982

Atten: State of Kansas  
State Corp. Commission


POP June 18, 1982, - Finaled for 15 BOPD and 200 BW. Water broke in, Pump 850 BWPD for 2 weeks, no oil. Swabbed (2) days @ 20 BFPD with no show of oil. Produced a total of 200 BO.

Set Bridge Plug @ 3815 - Perforate Viola from 3774-3776, 3754-3756, 3734, 3734, 3742.

Acidized with 500 gal. 15% intensified non-swell. No show - no fill up.

Plugged per front side.

Signed:

  
HUPFER OIL & GAS  
DENNIS D. HUPFER

