


WELL PLUGGING RECORD

Give All Information Completely Make Required Affidavit Mail or Deliver Report to Conservation Division State Corporation Commission 300 Bittling Building Wichita, Kansas

Pawnee County, Sec. 11 Twp. 21 Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines Lease Owner T. L. Nutt Lease Name E. J. Bowman Well No. 1 Office Address Ellinwood, Kans. Character of Well (completed as Oil, Gas or Dry Hole) Oil Date well completed 1/21/ 19 48 Application for plugging filed 8/22/ 19 57 Application for plugging approved 8/23/ 19 57 Plugging commenced 8/24/ 19 57 Plugging completed 9/1/ 19 57 Reason for abandonment of well or producing formation Not paying



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 7/22/ 19 57 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Brundage Producing formation Depth to top Bottom Total Depth of Well Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Contains data for casing sizes 5 1/8, 8, and 13 inches.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3788 to 3770 ft. Sand bridge. 3770 to 3745 5 Skcs.cement by dump bailer. 3745 to 420 Mudded,showled in. 420 to 400 Rock bridge. 400. to 340 20 Skcs,.cement, showled in. 340 to 20 Mud,showled in. 20 to Cellar 5 Skscement,showled in.

FEB 12 1958 2-12-1958

CONSERVATION DIVISION Wichita, Kansas STATE CORPORATION COMMISSION

Name of Plugging Contractor R. & S. Pipe Pulling Co. Address Ellinwood, Kans. License # 1

STATE OF KANSAS COUNTY OF BARTON ss. T. L. NUTT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt Boy 407 - Ellinwood, Ks (Address)

SUBSCRIBED AND SWORN to before me this 11 day of February, 19 58 Eusebio R. DeVore Notary Public.

My commission expires Mar. 21, 1959

PLUGGING FILE SEC 11 T. 21 R. 16W BOOK PAGE 39 LINE 13


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bldg. Wichita, Kansas

Company - GULF OIL CORPORATION  
Farm Earl J. Bowman No. 1

SEC. 11 T. 21 R. 16W  
NE NE SW

Total Depth. 3788'  
Comm. 12-15-47 Comp. 1-21-48  
Shot or Treated. Acidized: w/500 gals(1-19-48)  
Contractor.  
issued. 3-20-48

County. Pawnee  
KANSAS



Elevation. ....

Production. 6,890B0 no Wtr.PD

CASING:

13 3/8" @ 42'  
8 5/8" @ 993'  
5 1/2" @ 3788' -100' sks

Figures indicate Bottom of Formations.

surface clay & sand	44
sand	128
sand & gravel	150
shale & shells	200
shale & gyp	270
shale & shells	385
pyrite	405
sand	515
red bed	695
red bed & shells	750
sandy shale & shells	835
red bed	992
anhydrite	1020
red bed & shale	1260
shale	1890
lime	1900
shale & shells	1970
lime & shale	2085
shale & shells	2205
lime & shale	2257
broken lime & shale	2345
lime & shale	2480
broken Lime & shale	2695
shale & lime	2805
broken lime & shale	2870
lime	3045
broken lime & shale	3075
lime & shale	3170
broken lime & shale	3215
lime & shale	3705
cherty lime & shale	3754
cherty lime	3770
lime & shale	3788

3790-5 sks  
400 20 sks  
205 sks

Total Depth

Indicated Capacity State Test -  
6,890 bbls Oil, No Wtr., 24 hrs.

TOPS:

Stone Corral	784
Heebner	3323
Toronto	3348
Base Oread	3359
Lansing	3432
Base Kansas City	3668
Viola	3706
Simpson	3753
Arbuckle	3787

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 1 1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 11 T. 21 R. 16W  
BOOK PAGE 39 LINE 13

3788  
 500'  
 ---  
 3288

94  
 90  
 ---  
 3760  
 34  
 35  
 ---  
 3790 37 string  
 282  
 ---  
 3290  
 185  
 ---  
 3470

182  
 185  
 L  
 P  
 182  
 185  
 182  
 185  
 182  
 185  
 182  
 185  
 182  
 185

182  
 185

182 185 182 185

182  
 185  
 182  
 185

182  
 185

182  
 185