

ATE OF KANSAS  
ATE CORPORATION COMMISSION  
D. S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 15-145-20,967-0000

LEASE NAME Bowman "B"

TYPE OR PRINT RECEIVED  
NOTICE: Fill out KANSAS CORP COM  
and return to Cons. Div.  
office within 30 days - 5

WELL NUMBER 3

4290' Ft. from S Section Line

330' Ft. from E Section Line

EASE OPERATOR John H. Shaida

SEC. 11 TWP. 21 SRGE. 16W (E) or (W)

DRESS 4126 N. Sweet Bay Circle Wichita, Ks. 67226

COUNTY Pawnee

PHONE (316)636-2525 OPERATORS LICENSE NO. 3833

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 5-21-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-26-98

The plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3796'

Describe in detail the depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	969	None
				5-1/2"	3795'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 3735' and 5 sks. cement. Shot pipe @2600', 2500', 2400'. Pulled up to 1000', pumped 10 sks. gel, 50 sks. cement, pulled to 500', pumped 40 sks. cement. Circulated 10 sks. cement from 40' to surface. Plugging Complete. 60/40 pos. 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Mike's Testing & Salvage, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1998

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

