

ATE OF KANSAS  
ATE CORPORATION COMMISSION  
D. S. Market, Room 2078  
Chfta, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145-20,905-0000

LEASE NAME Bowman

WELL NUMBER B-1

3950 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 11 TWP. 21S RGE. 16W (E) or (W)

COUNTY Pawnee

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-6-98

Plugging Completed 7-14-98

RECEIVED  
KANSAS CORP. NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.  
1998 JUL 20 2:26

EASE OPERATOR John H. Shaida 7-20-1998

ADDRESS 4125 North Sweet B Wichita, Ks. 67226

PHONE# (316) 636-2525 OPERATORS LICENSE NO. 3833

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	952'	None
				5-1/2"	3796'	2618'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 3740' and 5 sacks cement. Shot pipe @2618', pulled up to 980', pumped 10 sks. gel and 50 sks. cement, pulled to 500', pumped 40 sks cement, pulled to 40' and circulated 10 sks. cement. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Mike's Testing & Salvage, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of July, 1998

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

