


WELL PLUGGING RECORD

Get All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 25 Twp. 21 Rge. 14 (A) (W)

Location as "NE/CNW/SW" or footage from lines SE/SE/NE  
Lease Owner Morgenstern Oil Properties  
Lease Name H. Baier Well No. #2  
Office Address Box 661, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed Yes 19\_\_\_\_  
Application for plugging approved Yes 19\_\_\_\_  
Plugging commenced \_\_\_\_\_ 11-21 19 57  
Plugging completed \_\_\_\_\_ 11-27 19 57  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Brundedge  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3760' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,016'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into T.D. 3760'.  
Plugging started 11-21-57. Finished 11-27-57.  
Sanded back to 3740' and dumped 5 sacks cement. Worked and shot pipe.  
Layed down pipe. Squeezed well. Pumped 20 sacks mud and 80 sacks cement.  
Well completed.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes  
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 1957  
Betty S. Edman Notary Public.

My commission expires November 8, 1960.

PLUGGING  
FILE SEC. 25 T. 21 R. 14W  
BOOK PAGE 42 LINE 40

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY GRAHAM-MESSMAN-RINEHART OIL CO.

SEC. 25 T. 21 R. 14W  
LOC. SE SE NE

FARM H. Baier NO. 2

TOTAL DEPTH 3748

COMM. 1-21-51


COMP. 2-1-51

COUNTY Stafford

SHOT OR TREATED

CONTRACTOR G-M-R.

ISSUED 3-3-51



CASING

8 5/8" 194' cem. w/150 sx.  
5 1/2" 3755' cem. w/175 sx.

ELEVATION 1920 D.F.

PRODUCTION 100 bbls. / no wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

shale	194
shale & shells	815
anhyd.	840
shale	1336
lime & shale	1830
lime	1975
limo & shale	2998
lime	3641
congl.	3690
limo & shale	3744
Arb.	3748
Total Depth	

Tops:	
Anhyd.	840
Congl.	3690
Arbuckle	3748

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 21 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING	
FILE	SEC. 25 T. 21 R. 14W
BOOK	PAGE 62 LINE 40