

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 25 Twp. 21 Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Morgenstern Oil Operations
Lease Name Baier "A" Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12-20-61 _____ 19____
Plugging completed 12-27-61 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lac Kamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3745 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	205'	None
				5-1/2"	3741'	2001'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3745', sanded to 3725' and dumped 5 sacks of cement @ 3725' with dump bailer. Pulled 5 1/2" casing. Set rock bridge from 200' to 190' and dumped 10 sacks of cement @ 190' with dump bailer. Bailed off fluid, found top of cement @ 160' and ran 10 sacks of cement @ 160'. Mudded hole to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1962

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

1-23-1962

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 62

My commission expires May 20, 1964 Milton J. Volin Notary Public.



COPY

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY GRAHAM-LESSMAN-RINEHART OIL CO.

SEC. 25 T. 21 R. 147
LOC. NE NE SE

FARM Baier "A"

NO. 1

TOTAL DEPTH 3745

COMM. 12-10-50

COMP. 12-24-50


SHOT OR TREATED

CONTRACTOR G-M-R Oil Co.

ISSUED 2-17-51

COUNTY Stafford

KANSAS



8 5/8" ⁵⁰⁰⁰205" cem. w/150 sx.
5 1/2" 3741 cem. w/85 sx.

ELEVATION 1926 D. T.

PRODUCTION 242 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

shale	205
shale & shells	830
anhyd.	865
shale & shells	1591
shale & lime	1910
lime & shale	2220
shale & shells	2756
lime	2785
lime & shale	3100
lime	3285
lime & shale	3360
lime	3622
lime & shale	3688
S. sand, shale	3714
shale & lime	3745
Total Depth	

Tops:	
Huebner shale	3261
Brown Lansing	3382
White Lansing	3393
W. Viola	3641
S. shale	3685
Arbuckle	3740

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1961

CONSERVATION DIVISION
Wichita, Kansas