

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford

County. Sec. 25 Twp. 21 Rge. 11W (W)

Location as "NE/CNW/SW" or footage from lines W/2 SE

Lease Owner Clay Newell & et al

Lease Name Raier Well No. 1

Office Address Stafford, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 19

Plugging completed October 19, 1962

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp

Producing formation Depth to top Bottom Total Depth of Well 3765' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand from 3607' to 3580'. Run 4 sacks of cement from 3580' to 3500'. Mud from 3500' to 200'. Rock bridge from 200' to 190'. Run 20 sacks of cement from 190' to 130'. Mud from 130' to 40'. Rock bridge & 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1965

CONSERVATION DIVISION
Wichita, Kansas 3-15-1965

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Casing Pulling Co.
Address Ellinwood, Kansas #396

STATE OF _____, COUNTY OF _____, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clay Newell
Stafford, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of March, 1965
Seward S. Greuber
Notary Public.

My commission expires 11-5-67

15.185.01188.0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company. KING OIL CO.
Farm. Baier No. 1

SEC. 25 T. 21 R. 14W
SW SW SE

Total Depth. 3765'
Comm. 3-16-61 Comp. 3-24-61
Shot or Treated.
Contractor. Garvey Drig. Co.
Issued. 3-10-62

County Stafford
KANSAS



CASING:
8 5/8" 248' cem w/225 sx.
4 1/2" 3764' cem w/125 sx.

Elevation. 1926' DF

Production. 25 BOPD

Figures Indicate Bottom of Formations.

surface soil & sand	196
blue shale	255
sand	390
shale & shells	840
shale	1410
shale & shells	1590
shale & lime	1830
lime	2220
lime & shale	2370
shale & lime	3030
lime	3298
lime & shale	3415
lime	3719
shale	3755
lime	3765
Total Depth	

TOPS: SCOUT	
Anhydrite	810
Heebner	3275
Toronto	3300
Brown Lime	3397
Lansing	3406
Conglomerate	3662
Viola	3674
Simpson	3722
Arbuckle	3762

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION
Wichita, Kansas

15.185.01188.0000

INVOICE

Ralph Glenn
Phone 449-R

Glenn & Smith Pipe Pulling Co.

R. E. Smith
Phone 582-R

Box 114

ELLINWOOD, KANSAS

Date 10 / 22 / 62

Sold To: CLAY NEWELL
STAFFORD, KANSAS.

Invoice No. 33

Well No. 1

Sec. 25 - 21 - 14 w

Lease. B Raier

10/17/62	Cleaning out cellar, rigging up, filled with sand from 3607' to 3580' and run 4 sacks of cement from 3580' to 3500'.	7 hrs.	\$ 49.00
10/18/62	Working 20" tension in 4 1/2" pipe shot at 2980' and started 4 1/2" and pulling pipe.	2 hrs.	14.00
10/19/62	Mudded from 3500' to 200' rock bridge 200' to 190' run 20 sacks of cement from 190' to 130' mudded from to 40' rock and 10 sacks of cement from 40' to base of cellar.	7 hrs.	49.00
	16 hrs. @ 7.00 per hr		112.00
	1 shot @ \$ 10.00 per shot		10.00
	2990' 4 1/2" @ .20 per foot		598.00
			\$ 720.00

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1962

CONSERVATION DIVISION
Wichita, Kansas

PERMIT NO. 396
STATE PLUGGER: W. L. LACKAMP

THANK YOU