


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD



NORTH

Locate well correctly on above  
Section Plat

Stafford County. Sec. 25 Twp. 21S Rge. 14 (X) (W)  
Location as "NE/CNW/SE" or footage from lines SW NW SE  
Lease Owner The El Dorado Refining Company  
Lease Name Matteson Well No. 1  
Office Address 306 Koch Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 12-1-55 19  
Application for plugging filed 12-1-55 19  
Application for plugging approved 12-1-55 19  
Plugging commenced 12-1-55 19  
Plugging completed 12-1-55 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes, verbally

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation Arbuckle Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3808 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Top soil, sand & shale		0	211	8 5/8	211	none
Heebner		3281				
Toronto		3302				
Douglas		3323				
Brown Lime		3404				
Lansing		3414				
Conglomerate		3675				
Viola		3680				
Simpson		3743				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud and 1/3 sax hulls, set Halliburton plug at 205'  
and 20 sax cement, put in 1/3 sax hulls, set Halliburton plug at 40' and  
10 sax cement, leveled location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ben F. Brack Oil Company, Inc. (drilling contractor)  
Address 309 Brown Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Bernard D. Grant (acting agent) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Bernard D. Grant  
309 Brown Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of December 19 55

Gertrude Crist  
Notary Public.

My commission expires June 11, 1959

PLUGGING  
FILE SEC 25 T 21 R 14W  
BOOK PAGE 21 LINE 23

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 6 1955  
12-6-1955  
CONSERVATION DIVISION  
Wichita, Kansas

BEN F. BRACK OIL COMPANY, INC.  
309-10 BROWN BUILDING  
WICHITA 2, KANSAS

MATTESON #1

SW NW SE

Sec. 25-21S-14W  
Stafford County, Kansas  
Commenced: 11-19-55  
Completed: 12-1-55

TOTAL DEPTH: 3808'

WELL LOG

Top Soil & Sand	0 -	90'
Sand & Shale		360
Red Bed & Shale		810
Anhydrite		850
Shale & Shells		1510
Shale & Lime		1725
Lime & Shale		2080
Shale & Lime		2225
Lime & Shale		2415
Shale & Shells		2605
Shale, Shells & Lime		2790
Shale & Shells		2900
Lime & Shale		2972
Lime, Shale, & Shells		3045
Shale & Lime		3110
Lime & Shale		3584
Lime		3636
Lime & Shale		3703
Shale & Lime		3710
Lime		3750
Shale & Lime		3805
Lime & Shale		3808 T.D. D. & A.

The above depths denote bottom of formations.

CASING

8 5/8" 211'

To the best of my knowledge, the above is a true and correct statement of the depths and formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By Bernard D. Grant

PLUGGING  
FILE SEC 25-21S-14W  
BOOK PAGE 21 LINE 23

WITNESSED:

Artrude Crist

December 5, 1955.

RECEIVED  
DEC 6 - 1955  
CONSERVATION DIVISION  
Wichita, Kansas