


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 25 Twp. 21 Rge. 14 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner B. E. Ash, Ellinwood, Kansas
Lease Name Parker Well No. 1
Office Address Box 211, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 24, 19 57
Application for plugging filed February 23 19 57
Application for plugging approved February 23 19 57
Plugging commenced February 24 19 57
Plugging completed February 24 19 57
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundege, Box 283, Hoisington, Kansas
Producing formation None Depth to top Bottom Total Depth of Well 3830 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	346'	8 5/8"	346.27'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug - 210'
20 sacks cement
Top Plug - 20'
5 sacks cement
Cement to bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bea Drilling Company
Address Box 211, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
B. E. Ash (~~employee of owner~~) (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B E Ash
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of March

Virgil E. Belford, Jr. 19 57
Notary Public. **RECEIVED**
MAR 5 - 1957
STATE CORPORATION COMMISSION
Wichita, Kansas

My commission expires April 27, 1957

PLUGGING
FILE SEC 25 T. 21 R. 14W
BOOK PAGE 143 LINE 38

STATE CORPORATION COMMISSION
MAR 4 1957
Secretary

B. E. ASH, ET AL
 #1 Parker
 SW SW SW Sec. 25-T21S-R14W
 Stafford County, Kansas

Commenced Rigging up	2-11-57	Elevation GR	1933
Commenced Drilling	2-12-57	Elevation DF	1936
Completed	2-24-57	Elevation RB	1938
Total Depth	3830'	Initial Production	Dry
		Contractor	Bea Drilling Co.
		Tools	Rotary

CASING RECORD

Run 346.72' 8 5/8", 225 sacks cement Pulled None Left In 346.72' 8 5/8" casing

<u>Strata</u>	<u>Depth</u>	<u>Formation Tops R. B.</u> 3' above Derrick Floor	
Sand	0 - 225		
Sand shale	225 - 290	Heebner	3297 -1359
Shale & shells	290 - 310	Toronto	3320 -1382
Cement	310 - 347	Douglas	3336 -1398
Shale & shells	347 - 354	Brown Lime	3419 -1481
Red Rock	354 - 490	Lansing-K. C.	3429 -1491
Red Bed & shale	490 - 820	Viola	3698 -1760
Anhydrite	820 - 855	Simpson	3740 -1802
Shale & shells	855 - 1345	Arbuckle	3788 -1850
Salt	1345 - 1490	Rotary T. D.	3830 -1892
Salt & shale	1490 - 1550		
Shale & shells	1550 - 1655		
Lime & shale	1655 - 3510		
Lime	3510 - 3614		
Lime & shale	3614 - 3670		
Lime	3670 - 3720		
Lime & shale	3720 - 3830		
Total Depth	3830		

I certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 5 - 1957
 CONSERVATION DIVISION
 Wichita, Kansas

B. E. Ash
 B. E. Ash

STATE OF KANSAS)
 COUNTY OF BARTON) SS

Subscribed and sworn to before me this 1st day of March, 1957.

Virgil E. Belford, Jr.
 Virgil E. Belford, Jr. Notary Public

My commission expires: April 27, 1957

PLUGGING
 FILE SEC. 25 T. 21 R. 14W
 BOOK PAGE 143 LINE 38

STATE CORPORATION COMMISSION
 MAR 4 1957
 Secretary