

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 27 TWP. 21S RGE. 12W E/W
Location as in quarters or footage from lines:
C NW NW

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Meltzer Oil Company
Lease Name Shumway #3 Well No. _____
Office Address P.O. Drawer B Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 12-3-81
Plugging completed 12-8-81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz
Producing formation _____ Depth to top _____ bottom _____ T.D. 3598'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 260' | none |
| | | | | 5-1/2" | 3578' | 2702' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3225' and set 5 sacks cement. Shot pipe @2901' and 2800'. Pulled a total of 83 joints of pipe. Plugged well with 4 sacks hulls, 25 sacks gel 1 sack hulls, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc. Plugging Completed.

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1982

CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 1981



Irene Hoover
Notary Public.

My Commission expires: _____

DRILLER'S WELL LOG

DATE COMMENCED: 10-20-79
DATE COMPLETED: 10-26-79

Meltzer Oil Company
Shumway #3
C NW NW, Sec. 27-21s-12w
Stafford County, Kansas

ELEVATION: K.B.

FORMATION DATA

| | |
|-----------|----------------|
| 111-3116' | Anhydrite |
| 116-3129' | Shale |
| 129-3145' | Lime |
| 145-3248' | Lime |
| 248-3261' | Shale |
| 261-3494' | Lime and Shale |
| 494-3518' | Lime |
| 518-3577' | Chert |
| 577-3579' | Sand |
| 3579' | Dolomite |
| | RTD |

| | |
|------------|------|
| Anhydrite | |
| Heebner | 3111 |
| Toronto | 3129 |
| Douglas | 3145 |
| Brown Lime | 3248 |
| Lansing | 3261 |
| Viola | 3494 |
| Simpson | 3518 |
| Arbuckle | 3577 |
| RTD | 3579 |

SURFACE PIPE:

Ran 6 Jts. Used 28#, 8 5/8" Csg.
Tally 255'. Set @ 260' w/250 sks.
60-40 Pozmix, 2% Gel, 3% c.c.
By Allied. P.D. @ 10:30.
Cement Circulated.

PRODUCTION PIPE:

Ran 111 Jts. Used 14#, 5 1/2" Csg.
Tally 3581'. Set @ 3578' w/100 sks.
60-40 - 18% salt & 15 bbl. Flush
P.D. @ 4:00 a.m. 10-26-79

A F F I D A V I T

RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1981


STATE OF KANSAS }
COUNTY OF BARTON } ss.

DALE L. SMITH, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

CONSERVATION DIVISION
Wichita, Kansas

Dale Smith

Subscribed and sworn to before me this 1st day of November 1979.



Wanda Oude
Notary Public

My commission Expires: 1-28-1980.