

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-21111-00-01
Spot: SWSESE Sec/Twnshp/Rge: 10-25S-12W
333 feet from S Section Line, 994 feet from E Section Line
Lease Name: MCFADDEN Well #: 1
County: STAFFORD Total Vertical Depth: 4245 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4095		
PROD	4.5	4225	0	WITH 275 SX CMT
SURF	8.625	336		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/01/2017 8:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: RANDY GNIEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: SET CIBP @ 3270' WITH 2 SX CMT. TEST CASING, PERFORATE AT 720' WITH 10 SX GEL & 50 SX CMT WITH HULLS IN LAST 25 SX. PERFORATE AT 360' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2017 2:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

PERFORATIONS WERE SQUEEZED WITH 35 SX CMT WITH HULLS ADDED. CASING WAS PRESSURE TESTED TO 200 PSI & HELD. BOTTOM PLUG TAGGED AT 3430'. PERFORATE AT 720' & 360'. TIH WITH 2 3/8" TBG TO 720'. ESTABLISH CIRCULATION WITH FRESH WATER THEN PUMP 10 SX GEL FOLLOWED BY 50 SX CMT WITH HULLS IN LAST 25 SX CMT. PULLED TBG TO 360' & PUMPED 40 SX CMT TO SURFACE. PULLED TBG & TOPPED OFF CASING & ANNULUS WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3956	3960		
3721	3723		


Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

INVOICED
SEP 27 2017

District: 01

Signed



(TECHNICIAN)

RECEIVED
SEP 11 2017
KCC DODGE CITY



5/A