

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22617-00-00
Spot: NWSWNESE Sec/Twnshp/Rge: 4-24S-5E
1930 feet from S Section Line, 1300 feet from E Section Line
Lease Name: PICKETT Well #: 9
County: BUTLER Total Vertical Depth: 2557 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2554		100 SX
SURF	8.625	220		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2017 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: ALAN NATION Company: RANGE OIL Phone: (620) 222-4304

Proposed Plugging Method: As per State instructions.

Plugging Proposal Received By: JONATHAN HILL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2017 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) Perf'd 4.5" casing at 270'
2) Ran in tubing to 2458' and spotted 35 sks class A cement w/ 4% CaCl. Full returns.
3) Pulled tubing up to 270'. Shut down for 1 hr.
4) Pumped 133 sks class A cement w/ 3% CaCl. Full returns, cement circulated to surface.

8/29/2017: Topped off casing w/ 15 sks cement

Perfs:

Top	Bot	Thru	Comments
2459	2471		

INVOICED
SEP 27 2017

Remarks: CEMENTING COMPLETED BY GRESSEL OILFIELD SERVICE, LLC. TICKET #: 44959. PLUGGED DUE TO COMPLIANCE W/ K.A.R. 82-3-111, DENIED TA.

Plugged through: TBG

District: 02

Signed Jon M Hill
(TECHNICIAN)