

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-017-20094-00-00
Spot: SWSW Sec/Twship/Rge: 20-18S-6E
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: FRIEDMAN(HART) Well #: 1
County: CHASE Total Vertical Depth: 770 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	756		150 SX
SURF	6.625	98		50 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/24/2017 12:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: BOB ROBINSON Company: SHAWMAR OIL & GAS CO., INC. Phone: (620) 382-2932

Proposed
Plugging
Method:

Run 1" to bottom, circulate cement to surface. Pull to 250'. Circulate to surface. Pull out 1". Top off hole.

Plugging Proposal Received By: JONATHAN HILL Witness Type: NONE
Date/Time Plugging Completed: 08/24/2017 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

- 1) Ran in 1" to 675' and hit bridge (approx. 75' below perfs)
- 2) Pumped 15 sks Class A cement, circulated to surface.
- 3) Pulled tubing up to 250, pumped and circulated additional cement to surface
- 4) Pulled tubing out of hole, topped off hole w/ cement.

Perfs:

Top	Bot	Thru	Comments
589	599		
542	552		

INVOICED
SEP 27 2017

Remarks: CEMENTING COMPLETED W/ COMPANY TOOLS. PLUGGED DUE TO COMPLIANCE AGREEMENT

Plugged through: TBG

District: 02

Signed Jean Hill
(TECHNICIAN)