

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-017-19044-00-00
Spot: SWSESWNE Sec/Twnshp/Rge: 19-18S-6E
2936 feet from S Section Line, 1732 feet from E Section Line
Lease Name: VESTRING TWIN Well #: 19-1
County: CHASE Total Vertical Depth: 635 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	626		0 SX
SURF	7	112		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/26/2017 12:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: BOB ROBINSON Company: SHAWMAR OIL & GAS CO., INC. Phone: (620) 382-2932

Proposed
Plugging
Method:

Run 1" to bottom, circulate cement to surface. Pull to 250'. Circulate to surface. Pull out 1". Top off hole.

Plugging Proposal Received By: JONATHAN HILL Witness Type: NONE
Date/Time Plugging Completed: 07/27/2017 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Perfs:

- 1) Ran in 1" tubing and tagged solid bridge at 510'. Can circulate from this depth. Verified 2.875" casing is cemented to surface.
- 2) Pumped 12 sks class A cement through 1" tubing, partial cement circulated to surface
- 3) Pulled tubing up to 250', circulated cement to surface.
- 4) Pulled 1" out of well, topped off w/ cement. Plugging complete

INVOICED
SEP 27 2017

Remarks: CEMENTING COMPLETED W/ COMPANY TOOLS. PLUGGED DUE TO COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed J. Hill
(TECHNICIAN)

1/2