

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-017-20899-00-00
Spot: NWSWNENW Sec/Twnshp/Rge: 35-18S-6E
918 feet from N Section Line, 1638 feet from W Section Line
Lease Name: LIPS Well #: 2-35
County: CHASE Total Vertical Depth: 945 feet

Operator License No.: <u>5192</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>SHAWMAR OIL & GAS CO., INC.</u>	CIBP		875		
Address: <u>1116 E MAIN PO BOX 9</u>	PROD	4.5	941		120 SX
<u>MARION, KS 66861</u>	SURF	8.625	200		75 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/08/2017 12:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: BOB ROBINSON Company: SHAWMAR OIL & GAS CO., INC Phone: (620) 382-2932

Proposed Plugging Method: Run 1" to bottom, circulate cement to surface. Pull to 250'. Circulate to surface. Pull out 1". Top off hole.

Plugging Proposal Received By: JONATHAN HILL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/08/2017 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) Cut down well head, tagged cement on backside of 4.5" at 8' from surface
2) Run in hole w/ tubing, tagged bridge plug at 875'. Pumped approx. 72 sks of 60/40/4% cement, circulated to surface
3) Pulled tubing up to 250', pumped 31 sks 60/40/4% cement, circulated to surface. Pulled tubing out
4) Hole staying full, will cut down casing and bury.

Perfs:

Top	Bot	Thru	Comments
892	898		
540	546		

INVOICED
SEP 27 2017

Remarks: CEMENTING COMPLETED BY QES, EL DORADO, KS. TICKET #: 54652. PLUGGED DUE TO COMPLIANCE W/ K.A.R. 82-3-111, DENIED TA (HIGH FLUID LEVEL).

Plugged through: TBG

District: 02

Signed [Signature] 1711
(TECHNICIAN)

JK