

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23599-00-00  
Spot: SENWNWNE Sec/Twnshp/Rge: 27-34S-10W  
657 feet from N Section Line, 1999 feet from E Section Line  
Lease Name: GATES Well #: 1  
County: BARBER Total Vertical Depth: 5380 feet

Operator License No.: 35053  
Op Name: TAPSTONE ENERGY, LLC  
Address: PO BOX 1608  
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4620		WITH 2 SX CMT
PROD	4.5	5132	750	WITH 210 SX CMT
SURF	10.75	218		WITH 230 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/06/2017 9:00 AM  
Plug Co. License No.: 35086 Plug Co. Name: SJL WELL SERVICE, LLC  
Proposal Rcvd. from: LARRY SETTLE Company: TAPSTONE ENERGY Phone: (620) 896-7200

Proposed Plugging Method: CIBP @ 4620' WITH 2 SX CMT. PLUG AT 620' WITH 12 SX GEL & 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/06/2017 1:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

CIBP @ 4620' WITH 2 SX CMT. CUT & PULL CASING AT 750'. 1ST PLUG AT 620' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 255' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 80 SX CMT TO FILL HOLE.

Perfs:

Top	Bot	Thru	Comments
4705	4714		
4670	4690		

INVOICED  
SEP 27 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

*Ken Scofield*  
51A

(TECHNICIAN)

RECEIVED  
SEP 14 2017  
KCC DODGE CITY

*MD*