

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21713-00-00
Spot: NENWENW Sec/Twnshp/Rge: 1-23S-24W
5044 feet from S Section Line, 3348 feet from E Section Line
Lease Name: RJD UNIT Well #: 1
County: HODGEMAN Total Vertical Depth: 4721 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
33856	CIBP		4570		WITH 2 SX CMT
Op Name: <u>WHITE EXPLORATION, INC.</u>	PROD	5.5	4720	0	WITH 400 SX CMT
Address: <u>1635 N. WATERFRONT PKWY SUITE 1</u> <u>WICHITA, KS 67206</u>	SURF	8.625	259		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2017 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: TERRY BAIRD Company: WHITE EXPLORATION Phone: (316) 641-8906

Proposed Plugging Method: SET CIBP @ 4570' WITH 2 SX CMT. RUN TBG TO 1600' & CIRCULATE TO SURFACE. PULL TBG & TOP OFF. PRESSURE BACKSIDE WITH CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/05/2017 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

9/1/17: MIKE MAIER ON LOCATION. SET CIBP @ 4570' WITH 2 SX CMT. RAN TBG TO 1626' & PUMPED 190 SX CMT. HAD GOOD CIRCULATION UNTIL RETURNS SHOWED SIGNS OF CMT, THEN LOST CIRCULATION. BACKSIDE WAS FULL. WILL TAG CMT ON TUESDAY. 9/5/17: TAGGED TOC AT 1000'. LAID THE TOP JOINT OF TBG DOWN LEAVING THE BOTTOM OF TBG AT 985'. CIRCULATED CMT TO SURFACE WITH 85 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4612	4616		

INVOICED
SEP 27 2017

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
SEP - 8 2017
KCC DODGE CITY

SA