

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22278-00-00
Spot: NESWSE Sec/Twnshp/Rge: 19-25S-5E
703 feet from S Section Line, 1959 feet from E Section Line
Lease Name: WRIGHT Well #: 6
County: BUTLER Total Vertical Depth: 775 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: 10500 E. BERKELEY SQUARE PKWY. S
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	680		
PROD	4.5	767		85 SX
SURF	7	50		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/12/2017 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Revd. from: DAN FLOWERS Company: _____ Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS. / SAND @ 550 W/4 SXS PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 09/12/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 560'. RIH W/TUBING @ 540', QES ESTABLISHED CIRCULATION, MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL 1 % CC TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #54760.

Perfs:

Top	Bot	Thru	Comments
752	764	CSG	

INVOICED
SEP 27 2017

Remarks: DENIED TA/ LENGTH OF TIME

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)