

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-21394-00-01
Spot: N2S2S2N2 Sec/Twnshp/Rge: 19-34S-11W
2030 feet from N Section Line, 2640 feet from W Section Line
Lease Name: LOGAN Well #: 1-X
County: BARBER Total Vertical Depth: 4770 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4600		WITH 2 SX CMT
PROD	4.5	4769	3035	WITH 150 SX CMT
SURF	8.625	370		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/28/2017 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4600' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 08/28/2017 6:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4600' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. 8/29/17: TOP OFF WELL WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4664	4702		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
JA (TECHNICIAN)

RECEIVED
SEP - 1 2017
KCC DODGE CITY

INVOICED
SEP 27 2017