

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20232-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 5-31S-16W
1250 feet from N Section Line, 1250 feet from W Section Line
Lease Name: GRB Well #: 1
County: COMANCHE Total Vertical Depth: 4818 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4750		WITH 2 SX CMT
PROD	4.5	4817	3228	WITH 125 SX CMT
SURF	8.625	452		WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/01/2017 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DEREK BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 4750' WITH 2 SX CMT. PLUG AT 900' WITH 12 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 09/05/2017 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

9/1/17: SET CIBP @ 4750' WITH 2 SX CMT. 1ST PLUG AT 900' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG PUMPED 55 SX CMT (30 SX CMT OVER) HAD CIRCULATION BUT NO CMT. SDFW. 9/5/17: TAGGED CMT AT 160' & TOPPED OFF WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4789	4812		

INVOICED
SEP 27 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Larry Harris
SA (TECHNICIAN)

RECEIVED
SEP 11 2017
KCC DODGE CITY