

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-00606-00-01
Spot: NWSESESE Sec/Twnshp/Rge: 26-9S-23W
395 feet from S Section Line, 370 feet from E Section Line
Lease Name: HILL CITY HIGH SCHOOL Well #: 1
County: GRAHAM Total Vertical Depth: 3945 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3942 | | 626 SX |
| SURF | 8.625 | 197 | | 105 SX |

Well Type: EOR UIC Docket No: E28555.2 Date/Time to Plug: 08/04/2017 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: OCTAVIO D MORALES Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations: 3712' - 3880'.
Alt II w/626 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/14/2017 12:20 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tubing parted at 2405'. Worked 9 days trying to fish out tubing. Could not get hold of tubing so decided to plug from there. Ran tubing to 2098' and pumped 290 sx cement. Good circulation of cement. Pulled tubing out. Tied on to casing and squeezed with 255 sx cement w/1000 # hulls. Casing on vacuum. Shut down.
Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.
08/14/2017 - Brought in redi mix truck and topped off casing with 40 sx cement. S & R Concrete Hill City Ks.

GPS: 39.23476 -099.84861

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3712 | 3880 | | |


INVOICED
SEP 26 2017

Remarks: SWIFT CEMENT TICKET # 30270

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA

SEP 14 2017

RECEIVED

AUG 22 2017