

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-19041-00-01  
Spot: NWSWNW Sec/Twnshp/Rge: 18-24S-13W  
3673 feet from S Section Line, 4959 feet from E Section Line  
Lease Name: HARRISON Well #: 3  
County: STAFFORD Total Vertical Depth: 4070 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>3493</u>	PROD	7	4070	0	WITH 600 SX CMT
Op Name: <u>FISHER, REGINALD D.</u>	SURF	10.75	227		WITH 200 SX CMT
Address: <u>110 N EXCHANGE ST</u> <u>SAINT JOHN, KS 67576</u>					

Well Type: EOR UIC Docket No: E24627.1 Date/Time to Plug: 09/13/2017 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: REGGIE FISHER Company: REGINAL FISHER Phone: (620) 793-2368

Proposed Plugging Method: SAND TO 3900' & 7 SX CMT. PERFORATE AT 850' & 260'. PICK UP TBG & ESTABLISH CIRCULATION. AT 850' PUMP 15 SX GEL FOLLOWED BY 75 SX CMT WITH 100# HULLS IN THE LAST 25 SX CMT. AT 260' PUMP CMT TO SURFACE. CONFIRM ANNULUS IS FULL OF CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/13/2017 2:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SAND BACK TO 3900' & TOP WITH 7 SX CMT. PLUG TAGGED AT 3800'.  
PERFORATE AT 850' & 260' WITH 4 SHOTS PER FOOT. PICK UP 2 3/8" TBG & TIH TO 850'. BREAK CIRCULATION WITH FRESH WATER & PUMP 12 SX GEL FOLLOWED BY 75 SX CMT WITH 100# HULLS IN LAST 25 SX CMT. PLUG TAGGED AT 600'.  
PULL TBG TO 260' & BREAK CIRCULATION WITH FRESH WATER. PUMP 70 SX CMT TO FILL 7" CASING TO SURFACE. PULL TBG. PUMP 30 SX CMT DOWN ANNULUS TO CIRCULATE INSIDE & OUT.

Perfs:

Top	Bot	Thru	Comments
3958	3964	CSG	

INVOICED  
SEP 27 2017

Remarks: USED COMMON CEMENT BY COPELAND.

Plugged through: TBG

District: 01

Signed

*[Signature]*  
5A

(TECHNICIAN)

RECEIVED  
SEP 14 2017  
KCC DODGE CITY