

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-20606-00-01
Spot: NWSWNWNE Sec/Twnshp/Rge: 13-9S-27W
4331 feet from S Section Line, 2348 feet from E Section Line
Lease Name: BREEDEN Well #: 1
County: SHERIDAN Total Vertical Depth: 4078 feet

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 2698 JO TERRACE
HILL CITY, KS 67642

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4065		300 SX
SURF	8.625	315		225 SX

Well Type: EOR UIC Docket No: E27377.1 Date/Time to Plug: 08/24/2017 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: LEON PFEIFER Company: RL INVESTMENT, LLC DBA Phone: (785) 421-6448

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.
8 5/8" surface casing set at 315' w/225 sx cement.
4 1/2" production casing set at 4065' w/300 sx cement. TOC from bond log: 2814'.
TD 4078', PBD 3958'.
4 1/2" production casing was perforated at 1985' and cemented with 560 sx cement. Poor bond log. No cement behind pipe at anhydrite.
Perforations: 3840' - 4065'.
Junk in hole: tubing with packer set at 3780'. Top of fish: 2400'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2017 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2307' and 1475'. Ran tubing to 2370' and pumped 80 sx cement. Pulled tubing to 1940' and pumped 175 sx cement w/50 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 40 sx cement. Connected to 8 5/8" surface casing and pumped 45 sx cement.

GPS: 39.27451N -100.28292W

Perfs:

Top	Bot	Thru	Comments
4028	4038		
4009	4016		
3992	3999		
3967	3976		
3912	3919		
3904	3912		
3886	3892		
3878	3882		
3866	3872		
3840	3848		
3822	3832		
3792	3796		

Remarks: SOS CEMENT TICKET # 605

Plugged through: TBG

District: 04

Signed Darrel Dipman
KCC WICHITA (TECHNICIAN)

CM

AUG 25 2017

SEP 14 2017

RECEIVED

INVOICED
SEP 27 2017