

1 120887

2-3

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 1963 15.185.19535.0000
NE NE NW, SEC. 16, T. 21 S, R. 11 W/EX
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8162

Lease Name Smith Estate Well # 13

Operator: L G W Energy Resources, Inc.

County Stafford

Name & Address 1000 W. 88th Terrace

Well Total Depth 3500 113.75 feet

Address Kansas City, MO 64114

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 p.m. Day: 3 Month: 2 Year: 19 94

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

logs: 5 1/2" at 3474' w/600 gal. Latex cement, PBTD 3385', Perfs at 3369-71'

1st plug sand back to 3300' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 3 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3315' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in: 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Pumping pressure 0-350 psi and shut in 100 psi.

FEB - 7 1994

Welded 8 5/8" plate with 4 1/2" collar.

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED (date of invoice) observe this plugging.

DATE FEB 11 1994

Signed [Signature] (TECHNICIAN)

INV. NO. 39919