

1060829

Docket No. D-10,380

API NUMBER 15- Comp. 12-22-61

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SE NW, SEC. 16, T 21 S, R 11 W/E  
3630 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8162

Lease Name Smith Estate Well # 4 SWD

Operator: LGW Energy Resources, Inc.

County Stafford 117.00

Name & Address P. O. Box 8651

Well Total Depth 3600 feet

Kansas City, MO 64114

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4" feet 279'

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:40 pm Day: 10 Month: March Year: 19 86

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3555'

1st plug sand back to 3500' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 1 sack hulls, 50 sx cement, 5 sx gel, 80 sx cement, released 10 3/4" rubber plug and pump 70 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:10 pm Day: 10 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 1 sack hulls, 50 sx cement, 5 sx gel, 80 sx cement, released 10 3/4" rubber plug and pumped 70 sx cement.

Remarks: Recovered 200' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton. (If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE MAR 20 1986

INV. NO. 13049

Signed Paul D. Luthie (TECHNICIAN)

MAR 20 1986