

1070119

TO: API NUMBER 15-185-23,020-0000
STATE CORPORATION COMMISSION 50'W 100'N C N/2 N/2 NW SEC. 20, T 21S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 230 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1270 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME KEELER "C" WELL # 2-20

TECHNICIAN'S PLUGGING REPORT 3/22 COUNTY STAFFORD 115.38

OPERATOR LICENSE # 5056 WELL TOTAL DEPTH 3550 FEET

OPERATOR: F.G. HOLL COMPANY, LLC PRODUCTION CSG: SIZE 4 1/2" @ 3545' WITH 225 SX

NAME AND PO BOX 780167 SURFACE CASING: SIZE 8 5/8" @ 267' WITH 220 SX

ADDRESS WICHITA, KS 67278

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 22 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 3470-72, 3414-18, 3439-44

SAND BACK TO 3335', DUMP 4 SX CEMENT. 1ST PLUG AT 1810' WITH 40 SX CEMENT. 2ND PLUG AT

600' WITH 50 SX CEMENT. 3RD PLUG AT 290' WITH 40 SX CEMENT. 4th PLUG AT 0-40' WITH 10

SX CEMENT. GOOD CIRCULATION THROUGHOUT JOB.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 22 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT _____

SAND BACK TO 3335', DUMP 4 SX CEMENT. 1ST PLUG AT 1810' WITH 40 SX CEMENT. 2ND PLUG AT

600' WITH 50 SX CEMENT. 3RD PLUG AT 290' WITH 40 SX CEMENT. 4TH PLUG AT 0-40' WITH 10

SX CEMENT. GOOD CIRCULATION THROUGHOUT JOB.

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2006' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

SIGNED

DATE 3/29/00

WZ NO. 06/478

(TECHNICIAN)

FORM CH MAR 27 2000

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED

STATE CORPORATION COMMISSION