

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22924-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 20-21S-11W
300 feet from N Section Line, 400 feet from W Section Line
Lease/Unit Name: KEELER C Well Number: 1-20
County: STAFFORD Total Vertical Depth: 3600 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 6427 EAST KELLOGG
WICHITA, KS 67207

Conductor Pipe: Size feet: #117.00
Surface Casing: Size 8.625 feet: 279 WITH 225 SX CMT
Production: Size 5.5 feet: 3594 WITH 225 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/07/2002 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TERRY BAIRD Company: F.G. HOLL Phone: (316) 684-8481

Proposed Plugging Method: SAND BACK TO 3395' & 5 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/07/2002 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 3581'. PERFS AT 3451-3461 & 3477-3484'. SANDED BACK TO 3395' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 20 2002

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GLE BY ACID SERVICES. RECOVERED 1810' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

MAR 11 2002

DATE

Mar 20-02

INV. NO.

2002061543

Form 2-2/3