

1 080550

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,480-0000

NE NW, SEC. 29, T 21 S, R 14 W/E  
4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6769

Lease Name Weirauch Well # 1

Operator: Westmore Drilling Co.

County Stafford 122.82

Name & Address Chapin Bldg., Box 347

Well Total Depth 3779 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:50 a.m. Day: 23 Month: 9 Year: 1986

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 3778' Perfs at 3742-45, 3734-36, 3771-75 Elevation 1944' GL  
PBTD 3760'

1st plug sand back to 3520' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls and 120 sx econolite

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 a.m. Day: 9 Month: 9 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sand back from 3760'-3520' and dumped 5 sx cement on top of sand through bailer

2nd plug squeezed well with 2 sx hulls and 120 sx Halliburton Light.

Maximum pressure 100 psi and shut in at 100 psi.

Remarks: Used Halliburton light by Halliburton. Recovered 1700' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(If desired, observer observe this plugging.)

**INVOICED**

DATE 9-30-86

SEP 30 1986

Signed \_\_\_\_\_ (TECHNICIAN)

INV. NO. 15035-9-23

9-30-1986