

12-12

Docket #D-23,833

API NUMBER 15- 145-21,162.0000

1 120353

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE NE, SEC. 27, T 21 S, R 16 W/E

4950 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6988

Lease Name Bell Well # 2

Operator: Smith Oil Operations

County Pawnee 144.59

Name & Address P.O. Box 550

Well Total Depth 4449 feet

Hutchinson, KS 67504-0550

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 982

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 12 Month: 12 Year: 19 89

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 7" at 3694' Open hole Elevation 1977' GL DV'd at 1006' w/300 sx cement.

1st plug set CIBP at 3650' with 4 sx cement on top.

2nd plug pump 50 sx cement at 1020',

3rd plug pump 50 sx cement at 550',

4th plug pump 15 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 12 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3650' and dumped 4 sx cement on top,

2nd plug pumped through tubing at 1020' with 90 sx cement,

3rd plug pumped 5 sx cement in 10 3/4" X 7" annulus. Shut in pressure 800 psi.

Pressured 7" casing at 750#.

Remarks: Used light cement by B.J. Titan. No casing recovery.

(If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

JAN 19 1989

CONSERVATION DIVISION Wichita, Kansas

INVOICED

(If necessary) observe this plugging.

DATE 1-3-1990

Signed [Signature] (TECHNICIAN)

INV. NO. 26871