

To: 121011 1-19
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15.145.00081.0000
API NUMBER 15-Drilled 2/27/53
SW SW SE, SEC. 27, T 21 S, R 16 W/E
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3048
Operator: Bristol Resources Corporation
Name:
Address 6655 S. Lewis, Ste. 200
Tulsa, OK 74136

Lease Name Miles Well # 1
County Pawnee
Well Total Depth 3867 125.68 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 987

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 19 Month: 1 Year: 19 95

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage (phone) 316-938-2943

were: 5 1/2" at 3863' w/125 sx cement, Open hole 3863-67'

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 10 sx gel ahead of 50 sx cement at 1470', 3rd plug pump 50 sx cement at 1000',

4th plug pump 40 sx cement at 450', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:20 p.m. Day: 19 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3800' and dumped 5 sx cement

on top of sand through bailer,

2nd plug pulled 5 1/2" casing to 1470' and pumped in 5 1/2" casing with 10 sx gel and 50 sx cement,

3rd plug pulled casing to 1000' and pumped in 5 1/2" casing with 4 sx gel, 50 sx cement, 6 sx gel,

4th plug pulled casing to 400' and pumped in 5 1/2" casing with 50 sx cement,

5th plug pulled casing to 40' and circulated with 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(to be observed) observe this plugging.

DATE 2-1-95

INV. NO. 42122

Signed [Signature] (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1995