

1 120351

12-12

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,159.0000
100' S of
SW SE NW, SEC. 27, T 21 S, R 16 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 6988
Operator: Smith Oil Operations
Name & Address: P.O. Box 550
Hutchinson, KS 67504-0550

2870 feet from S section line
3630 feet from E section line
Lease Name Bell Well # 1
County Pawnee 125.55
Well Total Depth 3863 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 989

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 12 Month: 12 Year: 19 89

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 7" at 3860' Open hole Elevation 1990' GL

1st plug sand back to 3800' and dump 7 sx cement on top of sand through bailer,

2nd plug pump 5 sxs. hulls and fill with light cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 p.m. Day: 12 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 7" casing back to 3810' and dumped 6 sx cement

on top of sand through bailer,

2nd plug pumped into 10 3/4" surface casing with 500 lbs. hulls and 205 sx cement.

Pumping pressure 0-650 psi and shut in 500 psi.

RECEIVED STATE CORPORATION COMMISSION

DEC 19 1989

Remarks: Used light cement by B.J. Titan. Recovered 2300' of 7" casing. CONSERVATION DIVISION Wichita, Kansas
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-3-1990

INV. NO. 26870

Signed [Signature] (TECHNICIAN)