

1 120433

6-12 15.145.00777.0000

API NUMBER 15- Drilled 5/15/53

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SW, SEC. 27, T 21 S, R 16 W/E

2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Cossman "A" Well # 3

Operator: Phillips Petroleum Company

County Pawnee 125.45

Name & Address Rt. 3, Box 20 A

Well Total Depth 3860 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 994

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 11 Month: 6 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3854' cemented with 125 sx, Perfs at 3338-3860' (5 sets)

1st plug sand back to 3285' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 12 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3285' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 8 sx gel, 50 sx cement, 12 sx gel, 100 lbs. hulls. Circulated on backside, dug down with backhoe and found hole

in 8 5/8" at 7', welded, 8 5/8" still leaking from below 10', moved in pulling unit and ran tubing to 1048' and pumped 125 sx gel and 150 sx cement, pulled tubing to 330' and circulated cement to surface.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2900' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-25-90

INV. NO. 28448

Observe this plugging. JUN 20 1990

CONSERVATION DIVISION Wichita, Kansas

Signed Susan Rankin (TECHNICIAN)

6-20-1990