

1 120432

6-11 15.145.00778.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drilled 7/3/53

NE NW SW, SEC. 27, T 21 S, R 16 W/E

2310 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Cossman "A" Well # 4

Operator: Phillips Petroleum Company

County Pawnee 125.68

Name & Address Rt. 3, Box 20 A

Well Total Depth 3867 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 995

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 11 Month: 6 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3858' cemented with 125 sx, Open hole

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 11 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3800' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 8 sx gel, 50 sx cement, 12 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-250 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-25-90 JUN 20 1990

INV. NO. 28449 CONSERVATION
Wichita, Kansas

Signed Duane Rankin
(TECHNICIAN)