

1052260

TO: STATE CORPORATION COMMISSION

5-28

API NUMBER 15-145-20,956-0000  
C W/2 E/2 NE SEC. 11, T 21 S, R 16 W

OK

CONSERVATION DIVISION - PLUGGING SECTION 3960 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BOWMAN B WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY PAWNEE

OPERATOR LICENSE # 3833 WELL TOTAL DEPTH 3893' 126.53 FEET

OPERATOR: JOHN H. SHALDA PRODUCTION CSG: SIZE 5 1/2" FEET 3786'

NAME AND ADDRESS 4126 N. SWEET BAY CIRCLE SURFACE CASING: SIZE 8 5/8" FEET 960'

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKES TESTING AND SALVAGE INC LICENSE NUMBER 31529

ADDRESS P. O. BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 28 MONTH: MAY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKES KELSO

(COMPANY NAME) MIKES TESTING AND SALVAGE INC (PHONE) 316-938-2943

WERE: PERFORATIONS 3794-3893 4 1/2" LINER FROM 3769' TO 3893' WITH 60 SX CEMENT

SAND BOTTOM TO 3750' AND PLACE 5 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

SPOT PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 990' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT.

2ND PLUG AT 500' WITH 40 SX OF CEMENT. 3RD PLUG AT 40' WITH 10 SX OF CEMENT.

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 28 MONTH: MAY YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3750' AND PLACED 5 SX OF CEMENT ON TOP OF SAND.

PUMPED PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 990' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT RECEIVED KANSAS CORPORATION COMMISSION

2ND PLUG AT 500' WITH 40 SX OF CEMENT,

3RD PLUG AT 40' WITH 10 SX OF CEMENT

JUN 03 1998

JUN 03 1998

GOOD CIRCULATION THROUGH OUT THE PLUG JOB.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 2608 VOLUME OF 1 1/2" CASING (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) CONSERVATION DIVISION WICHITA, KS

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

INVOICED

DATE 6-8-98 INV. NO. 50696