

7-14

1052271

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
WICHITA STATE OFFICE BUILDING
WICHITA, KANSAS 67202

API number: 15-145-20,905.0000
NE SW NE SEC. 11, 21 S, 16 W
3960 feet from S section line
990 feet from E section line

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1998

CONSERVATION DIVISION
Wichita, Kansas

Operator license#3833 Lease Bowman B well#1

Operator: John H. Shaida County Pawnee

Address: 4126 N Sweet Bay Circle Well total depth 3800 feet 123,50
Wichita, KS 67226
Conductor Pipe: inch @ feet
Surface pipe: 8 5/8 inch @ 952 feet
Production Csg: 5 1/2 inch @ 3796 feet

Aband. Oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mikes Testing & Salvage License#31529

Address: PO Box 467, Chase, KS 67524

Company to plug at: Hour: 10:00 a.m. Day: 14 Month: July Year: 1998

Plugging proposal received from: Mike Kleso

Company: Mikes Testing & Salvage Phone: 316-938-2943

Were: Perforations 3796-3800 Sand bottom to 3740' and place 5 sx of cement on top of the sand with dump bailor Spot plugs through casing while pulling pipe.

1st plug at 980' with 10 sx of gel followed by 50 sx of cement.

2nd plug at 500' with 40 sx cement.

3rd plug at 40' with 10 sx cement.

Recommended 60/40 Pozmix 6% gel

Plugging Proposal Received by: Richard Lacey

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:20 a.m. Day: 14 Month: July Year: 1998

Actual plugging report:

Sanded bottom to 3740' and placed 5 sx of cement on top of sand. Pumped plugs through casing while pulling pipe.

1st plug at 980' with 10sx of gel followed by 50 sx of cement

2nd plug at 500' with 40sx of cement

3rd plug at 40' with 10 sx of cement

Good circulation through out the plug job.

Remarks: Used 60/40 Pozmix 6% gel by Allied

I did (X)/did not () observe the plugging.

Richard W. Lacey

(agent)

Form CP-2/3

INVOICED

DATE JUL 23 1998

INV. NO. 50994