

1052257

TO: STATE CORPORATION COMMISSION

5-12

API NUMBER 15-145-20,897.0001  
SE NE SW, SEC. 11, T 21 S, R 16 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2740 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

KANSAS CORP. CO.

LEASE NAME BOWMAN "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY: PAWNEE

OPERATOR LICENSE # 3833 WELL TOTAL DEPTH 3950 128.38 FEET

OPERATOR: JOHN H. SHaida PRODUCTION CSG: SIZE 5 1/2" FEET 3796'

NAME AND ADDRESS 4126 N. SWEET BAY CIRCLE SURFACE CASING: SIZE 8 5/8" FEET 972'

ADDRESS WICHITA, KS 67226

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-20,891 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKES TESTING AND SALVAGE INC LICENSE NUMBER 31529

ADDRESS P. O. BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 21 MONTH: MAY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKES KELSO

(COMPANY NAME) MIKES TESTING AND SALVAGE INC (PHONE) 316-938-2943

WERE: OPEN HOLE 3858-3950

SAND BOTTOM TO 3460' AND PLACE 5 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

SPOT PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 1000' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT.

2ND PLUG AT 500' WITH 40 SX OF CEMENT. 3RD PLUG AT 40' WITH 10 SX OF CEMENT.

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 12 MONTH: MAY YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3460' AND PLACED 5 SX OF CEMENT ON TOP OF SAND.

PUMPED PLUGS THROUGH CASING WHILE PULLING PIPE.

1ST PLUG AT 1000' WITH 10 SX OF GEL FOLLOWED BY 50 SX OF CEMENT

2ND PLUG AT 500' WITH 40 SX OF CEMENT,

3RD PLUG AT 40' WITH 10 SX OF CEMENT

LEFT A PACKER IN THE HOLE AT 3792' AND 190' OF FIBERGLASS TUBING

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 2600' OF 5 1/2" CASING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (BY) OBSERVED THIS PLUGGING.

INVOICED  
MAY 27 1998

SIGNED Richard W. Lacey  
(TECHNICIAN) FORM CP-2/3

DATE

INV. NO. 50634