

6-13-88 15-185-20282.0001 182 R
API #15-185-20,282-A

1 120101

API NUMBER 15- Completion Date 12/2/85

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NW, SEC. 25, T 21 S, R 14 (W/E)

3630 feet from S section line

2970 feet from E section line

Lease Name Gerhardt Well # 1A

County Stafford 122.43

Well Total Depth 3767 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 365

TECHNICIAN'S PLUGGING REPORT

Operator License # 3648

Operator: O.C.S. Inc.

Name & Address 2704B Nottingham

Hutchinson, KS 67502

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hutch Well Service License Number

Address

Company to plug at: Hour: 11 a.m. Day: 13 Month: 6 Year: 1988

Plugging proposal received from Ron Brooks

(company name) O.C.S. Inc. (phone) 316-669-1181

were: 5 1/2" at 3761' cemented w/200 sx cement Perfs at 3417-18' Elevation 1927' KB

1st plug sand back to 3365' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 13 Month: 6 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 3365' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION 6-21-1988 JUN 21 1988

Pumping pressure 0-700 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1840' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

(If possible) observe this plugging.

Signed Duane Rankin (TECHNICIAN)

INVOICED

DATE 7-15-88

INV. NO. 21354 6-13

AUG 3 1988 SEP 12 1988