

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20914-00-00
Spot: SESESWSE Sec/Twnshp/Rge: 27-21S-12W
150 feet from N Section Line, 150 feet from W Section Line
Lease/Unit Name: SHUMWAY Well Number: 1
County: STAFFORD Total Vertical Depth: 3632 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B WEST 10TH STREET
GREAT BEND, KS 67530

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 310 WITH 250 SX CMT
Production: Size 5.5 feet: 3634 WITH 175 SX CMT
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2001 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND BACK TO 3550' & 5 SX CMT. 1ST PLUG AT 660' WITH 50 SX CMT. 2ND PLUG AT 340' WITH 40 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.
118.04

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/26/2001 3:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3624-28, 3613-18, 3606-10'. ANHYDRITE @ 630-660'. SANDED TO 3300' AND 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 4-5-01
INV. NO. 2001061581

RECEIVED
STATE CORPORATION COMMISSION
APR - 5 2001
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2600' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey SA
(TECHNICIAN)

MAR 29 2001

Form CP-2/3

Handwritten initials and marks