

15.185.11695.0001

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address Rt. 2 Great Bend, Ks

Lease Name Lincoln Well No. 4

Location SW/NE/SE Sec. 29 Twp 21S Rge. 14 (E) (W) W

County Stafford Total Depth 3849

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated Replugged

Plugging Contractor Rockhold Engineering Co. Inc.

Address Box 698 Great Bend, Ks License No. 670

Operation Completed: Hour 10:00 AM Day 2 Month 6 Year 1972

The above well was plugged as follows:

279 ft 8 5/8 surface pipe cemented with 175 sacks. 3848 ft 5 1/2 long

string cemented with 100 sacks. Top perf. 3590 ft. Sand back to

3500 ft, 5 sacks cement with bailer. No pipe pulled. Pump 35 sacks

cement, 4% gel with 400 lbs pressure in casing.

Pumped by Globe Cementing Co. Great Bend, Ks

REPLUGGED

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor